| RAISE 3D | Raise3D OFP Test Report | | | | | |
|-------------------|--|---|------|---|-------|---|
| Basic Information | Material Fiberlogy Fiberflex 40D | | | | | |
| | Requirement | | | | | |
| Notes | 1. Dry the filament at 60 °C in a hot air dryer or vacuum oven for 4 hours before printing. | | | | | |
| Test Model | Printed Results | | | | | Printed Results Detail |
| Double Wall | ♦ | | | | | 1. Flowrate test is passed. |
| Raft Test | | | | | | The raft surface is clear and smooth. The infill flowrate of the square is suitable. |
| Angled Tube | | - | | | | The surface has less string. The contact face is smooth without heat disipati defects. No visible gap in the top beam of the model. The self-support is suitable without deformation |
| Block Peg | - | - | - | - | | The surface quality is good, The top surface is not collapsing or overflowing. The relief is very clear without ghosting, the top surface solid-fill flowrate is suitable. Layer start point is suitable. |
| Cube 555 | | • | | | | 1. Interlayer bonding test is passed. |
| Conclusion | 1. The optimised template has 2. Fiberlogy Fiberflex 40D is ea 3. Complex models have obvid 4. Thin-walled models are pro | asier to print than Fiberflex ous strings because the flex | 30D. | | cess. | ' |



Raft Test


Double Wall













Cube 555

Angled Tube



Block Peg







